

Donna Irrigation District  
Concrete Paving of the Bid Tabulation  
Concrete Paving of the East Main Canal and the  
North Crossover Main Canal  
Bid Opening Tuesday, September 24, 2024 @ 3P

**Bid Schedule A**

**BASE BID: Geosynthetic Composite Liner North crossover Main Canal and East Main Canal**

			Contractor: HUESKER, Inc.		Contractor: Western Environmental Liner						
Bid Item	Qty	Units	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	441,864	SF	Geosynthetic composite liner in seventeen foot wide rolls with freight to District office conforming exactly to the specifications for the unit price of:	\$ 0.83	\$ 366,747.12						
2	140	Bags	Holt Melt Adhesive in 33 lb. bags for the unit price of:	\$ 185.00	\$ 25,900.00						
3	34	Wks	Rental of 10L Adhesive Melter for the unit price of:	\$ 100.00	\$ 3,400.00						
<b>TOTAL AMOUNT BASE BID</b>				\$	396,047.12	\$	-	No Bid		No Bid	
<b>Delivery Time in Calendar Days from the issuance of the Purchase Order.</b>				Start Delivery 3 - 4 weeks		30 Days					

**Alternate Bid Schedule A**

**Alternate Geosynthetic Composite Liner North crossover Main Canal and East Main Canal**

Bid Item	Qty	Units	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	441,864	SF	Alternate geosynthetic composite liner proposed by the Supplier, delivered to the District office, meeting the specifications with all pertinent information from the manufacturer per specification, Division 2107, Part 2, submitted with this proposal, to be installed by a General Contractor and covered with a minimum of 3" of concrete or shotcrete for unit price of:			\$ 0.72	\$ 318,142.08				
2	441,864	SF	Joining system materials whether adhesive, or other material based on the gross amount of material to be joined for the unit price of:			No Charge	No Charge				
3	34	Wks	Rental of joining equipment as required for the unit price of:			No Charge	No Charge				
<b>TOTAL AMOUNT BASE BID</b>				No Bid		\$318,142.08		No Bid		No Bid	
<b>Delivery Time in Calendar Days from the issuance of the Purchase Order.</b>						30 days					
<b>4' x 4' Liner Sample included.</b>						Yes					
<b>Liner Submittal included.</b>						Yes					

**Bid Schedule B**

**Fabricated Stainless Steel Gates**

			Contractor: Fresno Valves and Castings, Inc.								
Bid Item	Qty	Units	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	2	Each	Manufacture and deliver 36" wide x 36" tall fabricated stainless steel slide gate with a total height of 89.6 inches from the flowline to the centerline of the gear operated lift supported by the frame, designed for 10 feet of seating head with a rising stem for the unit price of:					\$ 9,037.00	\$ 18,074.00		
2	2	Each	Manufacture and deliver 36" wide x 36" tall fabricated stainless steel slide gate with a total height of 101.3 inches from the flowline to the centerline of the gear operated lift supported by the frame, designed for 10 feet of seating head with a rising stem for the unit price of:					\$ 9,509.00	\$ 19,018.00		
3	2	Each	Manufacture and deliver 36" wide x 36" tall fabricated stainless steel slide gate with a total height of 108 inches from the flowline to the centerline of the gear operated lift supported by the frame, designed for 10 feet of seating head with a rising stem for the unit price of:					\$ 9,765.00	\$ 19,530.00		
4	10	Each	Manufacture and deliver 15" fabricated stainless steel canal gate with a frame height from the center of the pipeline to the top of frame from 5 to 7 feet, round flat back for wall mounting, with handwheel for the unit price of:					\$ 4,605.00	\$ 46,050.00		
5	11	Each	Manufacture and deliver 15" fabricated stainless steel canal gate with a frame height from the center of the pipeline to the top of frame from 7 to 9 feet, round flat back for wall mounting, with handwheel for the unit price of:					\$ 4,739.00	\$ 52,129.00		
6	1	Each	Manufacture and deliver 18" fabricated stainless steel canal gate with a frame height from the center of the pipeline to the top of frame from 7 to 9 feet, round flat back for wall mounting, with handwheel for the unit price of:					\$ 4,802.00	\$ 4,802.00		
7	1	Each	Manufacture and deliver 24" fabricated stainless steel canal gate with a frame height from the center of the pipeline to the top of frame from 7 to 9 feet, round flat back for wall mounting, with handwheel for the unit price of:					\$ 5,359.00	\$ 5,359.00		
8	1	Each	Manufacture and deliver one fabricated stainless steel, 24" wide downward opening weir gate with 30" of travel and a total frame height of 8' for the unit price of:					\$ 5,189.00	\$ 5,189.00		
<b>TOTAL AMOUNT BID</b>				No Bid		No Bid		\$ 170,151.00		No Bid	
<b>Delivery Time in Calendar Days from the issuance of the Purchase Order.</b>								12 Weeks			

Donna Irrigation District  
Concrete Paving of the Bid Tabulation  
Concrete Paving of the East Main Canal and the  
North Crossover Main Canal  
Bid Opening Tuesday, September 24, 2024 @ 3P

**Alternate Bid Schedule B**  
**Frames, Bronze Seats, Rising Stems**

**Cast Iron Gates with Stainless Steel**

Contractor:  
Fresno Valves and Castings, Inc.

Bid Item	Qty	Units	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
4B	10	Each	Manufacture and deliver 15" cast iron canal gate with 23 feet of seating head, a frame height from the center of the pipeline to the top of frame from 5 to 7 feet, round flat back for wall mounting, with bronze seats, rising stem and handwheel for the unit price of:					\$	2,659.00	\$	26,590.00
5B	11	Each	Manufacture and deliver 15" cast iron canal gate with 23 feet of seating head, a frame height from the center of the pipeline to the top of frame from 7 to 9 feet, round flat back for wall mounting, with bronze seats, rising stem and handwheel for the unit price of:					\$	2,923.00	\$	32,153.00
6B	1	Each	Manufacture and deliver 18" cast iron canal gate with 23 feet of seating head, a frame height from the center of the pipeline to the top of frame from 7 to 9 feet, round flat back for wall mounting, with bronze seats, rising stem and handwheel for the unit price of:					\$	3,668.00	\$	3,668.00
7B	1	Each	Manufacture and deliver 24" cast iron canal gate with 23 feet of seating head, a frame height from the center of the pipeline to the top of frame from 7 to 9 feet, round flat back for wall mounting, with bronze seats, rising stem and handwheel for the unit price of:					\$	4,221.00	\$	4,221.00
<b>TOTAL AMOUNT Base Bid Items 1-3 plus Alternate Bid Items 4B - 7B</b>						No Bid				\$66,632.00	
<b>Delivery Time in Calendar Days from the issuance of the Purchase Order.</b>										8 Weeks	

**Bid Schedule C**  
**BASE BID: Bypass System for the North Crossover Main Canal**

Contractor:  
Rain for Rent

Bid Item	Qty	Units	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	1	L.S.	Deliver and set up diesel driven bypass pumping system to include not less than two pumps rated for a minimum capacity of 20 cubic feet per second (cfs), one pump rated for not more than 10 cfs, discharge piping, valves and fittings, meter or meters to measure total flow, fused bypass line, diesel storage tanks, diesel containment pad and any other incidentals necessary, for the lump sum price of:							\$	121,848.63
2	4	Months	Monthly Rental for bypass system described above.							\$	84,390.62
3	3	Each	Relocate system described about 2,000 linear feet along canal for the unit price of:							\$	80,760.56
4	1	Each	Relocate system described about 2,000 linear feet along canal and across Hutto Road for the unit price of:							\$	80,760.56
5	1	L.S.	Disassemble and remove bypass system for the unit price of:							\$	61,535.69
<b>TOTAL AMOUNT BID</b>						No Bid				\$	843,989.04
<b>Delivery Time in Calendar Days from the issuance of the Purchase Order.</b>										14 Days	

Certified as Correct By:  
**FERRIS, FLINN & MEDINA, LLC**  
TBPE Firm No. F-897



9.25.24

Frank A. Ferris, PE

Date

