ADDENDUM NO. 3

To: All Planholders
From: Frank A. Ferris, PE
Subject: Hidalgo County Irrigation District No. 6
New River Pumping Facility
Date: November 3, 2026

The Contract Documents, Specifications & Plans are hereby modified as follows:

CONTRACT DOCUMENTS AND SPECIFICATIONS

I. **Section 00030 Invitation to Bid**
- Add the following provision to the "Bid Security" section of Page 00030-2, "Contract D – Supply and Delivery of 792 Linear Feet of 42" Class 165 C900 PVC Pipeline is exempt from this requirement."

II. **Section 00300B Bid Form (Proposal) Supply of Vertical Pumping Units**
- Replace Bid Schedule B with the attached Bid Schedule B - Addendum No. 3.

III. **Section 00300C Bid Form (Proposal) Supply of Natural Gas Engine**
- Replace Bid Schedule C with the attached Bid Schedule C – Addendum No. 3.

CONSTRUCTION PLANS

I. **Sheets S5, S6, S9**
- Clarification: The term "Driving Depth" refers to the Driving Line, NOT the pile tip.

II. **Sheet S6, Section 1 and Sheet 9, Section 4**
- Add the following note to the vertical (10) #8 steel reinforcement – "shall extend 36" below the pile cap".

Addendum No. 3 Issued by,
FERRIS, FLINN & MEDINA, LLC
TBPE Firm Reg. No. F-897

Frank A. Ferris, PE
President

11/3/26



Hidalgo County Irrigation District No. 6
New River Pumping Facility
Bid Schedule - Addendum No. 3

Contract B - Pumping Units

Bid Item	Quantity	Units	Description	Unit Price	Total Price
1	2	EA.	**Furnish and provide installation assistance** for two (2) 60cfs oil lubricated, 510 RPM mixed flow pumping units with 42 inch columns and 42 inch discharges, with 36 inch impellers built to the overall dimensions shown on the plans with stainless steel shafts, bronze impellers, epoxy coated, below ground discharges, including sole plates, certified tests, installations and startup assistance and all other incidentals necessary for the unit price of:		
2	1	L.S.	**Furnish and provide installation assistance** for a 3.5:1 air cooled right angle gear drive rated for a minimum of 375 HP input at 1800 RPM with driveshaft, couplings, u-joints, and driveshaft guard for the lump sum price of:		
3	1	L.S.	**Furnish and provide installation assistance** for a new 300HP, 460V, 3-Phase, 60Hz, 510rpm, WP-I Enclosure, High Thrust Electric Motor and accessories for the lump sum price of:		
			Total Amount Base Bid 'B':		

Time to deliver all equipment to job site: **Calendar days from receipt of Purchase Order**

Hidalgo County Irrigation District No. 6
New River Pumping Facility
Bid Schedule - Addendum No. 3

Contract C - Natural Gas Engine					
Bid Item	**Quantity**	**Units**	**Description**	**Unit Price**	**Total Price**
1	1	L.S.	**Furnish and provide installation assistance** for a new 325 BHP Natural Gas Engine and accessories including supply piping, cooling and exhaust systems, controls, field testing, and all other incidentals necessary for the lump sum price of:		
			Total Amount Base Bid 'C':		
Time to deliver all equipment to job site:				**Calendar days from receipt of Purchase Order**	